



1234 Del Este Avenue,
Suite 601
Denham Springs, LA 70726

T (225) 665-1021

F (225) 665-1022

PROJECT: JAHNCKE STREET OVERLAY
COVINGTON, LOUISIANA

ADDENDUM NO. ONE (1)
F&T JOB NO. 221324

DATE: DECEMBER 5th, 2022

TO: ALL OF RECORD HOLDING CONTRACT DOCUMENTS

GENERAL:

The following items shall be considered part of the Contract Documents and shall be included in same when Construction Contract is executed. Changes made by Addenda shall take precedence over original Documents. Any changes, which may affect construction or proper installation of materials, equipment or fixtures, not specifically mentioned in this Addendum, should be brought to the attention of the Engineer before submitting proposal. Otherwise, such conditions, if found later to exist, must be worked out in an acceptable manner without additional cost to the Owner. General Contractors are hereby advised to call attention of all subcontractors to changes, which may affect their work.

Acknowledge receipt of this Addendum by inserting its number and date in the proper blank appearing on the Bid form. Failure to do so may subject Bidder to disqualification.

GENERAL NOTE:

In order to provide responses to any and all remaining questions in a timely manner, Forte & Tablada asks that all contractor questions be submitted to our office no later than 2:00 PM DECEMBER 6th, 2022. Questions received after that time will not be answered.

CONTRACTOR QUESTIONS: Answers in **Bold after question.**

1. For the patching thickness, does the 12" minimum thickness include the overlay or is that in addition to the 12" minimum thickness? **Patching shall be done to conform to sections 509 & 510 of the DOTD 2016 Standard Specs. See note F on sheet 6 of the plans.**
2. Would the use of a rock saw be allowed for the necessary saw cutting of pavement at the end of the milling locations? **This would be acceptable provided saw cutting at all butt joints at the end of the milled pavement does not exceed the desired milling depth of 2" thick.**

3. Page 6, the joint repair detail, is that required to be used on this project? **Joint repair detail will be used in the event it is deemed necessary for repair work.**
4. For the line items 702-04-00100 (Adjusting Manholes) & 741-11-00100 (Adjusting Water Valves) is this item for only the removal and replacement for milling purposes or is this to be a full adjustment of the top ring of these items? **Manholes and water valves shall be adjusted as needed to ensure that the tops of the structure matches the surrounding pavement elevation after milling and overlay operations. Temporary or un-milled asphalt shall be utilized around existing manholes and valves between milling and overlay operations to prevent vehicular impacts.**
5. Please clarify the contract time is calendar day or working day. **Contract is to be completed on a calendar day basis.**
6. Please confirm there is no DBE (Disadvantage Business Enterprise) participation goal for this project. **No requirements for this project.**
7. Please provide the address to the City of Covington yard that the RAP will be delivered to. **1300 West 27th Ave.**
8. Will the city provide an operator to pile the RAP at the yard or will the contractor be required to supply equipment/operator at the yard to stockpile the RAP? **Contractor shall contact the city to schedule delivery time. 24 hr notice prior to RAP delivery is required, but contractor will not need to provide equipment/operator at delivery site.**

CONTRACTOR QUESTIONS (from Pre-Bid Meeting): Answers in **Bold** after question. See attached for sign in sheet from Pre-Bid.

1. What are the allowable work times? **During the week, lane closures are limited to between 9:00AM and 2:00PM. No work shall occur after 7PM in any case. Work hours may be extended to 7:00PM during the week if school is out. Any closures or work taking place on a holiday or weekend shall be prior approved by the City no later than close of business on the Thursday preceding the planned work.**